

142 B

ENERGY TECHNOLOGY ENGINEERING CENTER

OPERATED FOR THE U.S. DEPARTMENT OF ENERGY
ROCKETDYNE DIVISION, ROCKWELL INTERNATIONAL

DRG 7340325

No. SSWA-ZR-0001 Rev. ____

Page 1 of 72

Orig. Date 01/14/94

Rev. Date _____

SAFETY REVIEW REPORT (SRR)

TITLE: FINAL RADIOLOGICAL SURVEY REPORT OF BUILDING 064 INTERIOR

- APPROVALS -

Originator

[Signature]

F. C. Dahl/R. J. Tuttle

Fac Mgr

[Signature] 2-10-94

R. D. Meyer

Proj Mgr

[Signature]

G. G. Gaylord

RP&HPS

[Signature] 2/10/94

P. D. Rutherford

QA

[Signature]

T. D. Hunnicutt

REV.
LTR.

REVISION

APPROVAL/DATE

OFFICIAL COPY

FEB 14 1994

NOTICE: THIS COPY SUPERSEDES
ALL PRIOR COPIES ISSUED.

CONTENTS

	Page
1.0 Introduction	8
2.0 Summary and Conclusions	8
3.0 Background	9
3.1 Location	9
3.2 Topography and Building Characteristics	9
3.3 Operating History	16
3.4 Decommissioning and Demolition Efforts	17
4.0 Survey Results	19
4.1 Overview	19
4.2 Scope of the Survey	19
4.3 Survey Methods	22
4.4 Technical Approach	24
4.5 Sample Lot Analyses and Results	31
Appendices	
A Building 064 Interior Lots 1 through 3 Final Survey Data	56
B Building 064 Interior Lots 1 through 3 Final Survey Results	63

FIGURES

	Page
1. Location of SSFL in Relation to Los Angeles and Vicinity	10
2. Map of Neighboring SSFL Communities	11
3. Santa Susana Field Laboratory (SSFL) Area IV	12
4. Building 064 Plan View	14
5. Aerial Photo of Building 064, Viewing East Side	15
6. Building 064 Sample Lot Identification	21
7. Typical Room or Area 3-Meter by 3-Meter Grid Markings	23
8. Gamma Exposure Rate Measured in Building S445	26
9. Example of Sample Lot Acceptance Where $TS (= \bar{x} + ks) \leq UL$	30
10. Example of Sample Lot Requiring Additional Measurements Where $TS (= \bar{x} + ks) > UL$ and $\bar{x} < UL$	30
11. Example of Sample Lot Rejection Where $TS (= \bar{x} + ks) > UL$ and $\bar{x} > UL$	32
12. T064 - Lot 1 Total Alpha Activity	35
13. T064 - Lot 1 Removable Alpha Activity	36
14. T064 - Lot 1 Total Beta Activity	37
15. T064 - Lot 1 Removable Beta Activity	38
16. T064 - Lot 1 Floors Ambient Gamma Exposure Rate	39
17. T064 - Lot 2 Total Alpha Activity	43
18. T064 - Lot 2 Removable Alpha Activity	44
19. T064 - Lot 2 Total Beta Activity	45
20. T064 - Lot 2 Removable Beta Activity	46
21. T064 - Lot 2 Floors Ambient Gamma Exposure Rate	47

FIGURES

	Page
22. T064 - Lot 3 Total Alpha Activity	50
23. T064 - Lot 3 Removable Alpha Activity	51
24. T064 - Lot 3 Total Beta Activity	52
25. T064 Lot 3 Removable Beta Activity	53
26. T064 - Floors Ambient Gamma Exposure Rate	54

TABLES

	Page
1. Sample Lots Surveyed	20
2. Building 064 Contamination Limit Criteria	27
3. Observed Detection Limits versus Established Limit Criteria	27
4. Sample Lot 1 Results	33
5. Sample Lot 2 Results	41
6. Sample Lot 3 Results	48

ABSTRACT

A comprehensive radiological survey of Building 064 and its surrounding area at the SSFL was performed in 1988. In accordance with the recommendation made in that survey report, remedial efforts were undertaken to remove residual radioactively contaminated components from the Building 064 structure and grounds. After the decontamination efforts were completed, a comprehensive final survey of the building interior was performed to demonstrate regulatory compliance for release without radiological restrictions.

Results of surveys demonstrate that Building 064 meets the requirements of DOE, NRC, and State of California for releasing Building 064 for use without radiological controls.

REFERENCES

1. 154SRR000001, Radiological Survey Plan for SSFL, Rockwell International, dated September 25, 1985, F. H. Badger and R. J. Tuttle
2. GEN-ZR-0005, Radiological Survey of the Source and Special Nuclear Material Storage Vault - Building T064, dated August 19, 1988, J. A. Chapman
3. SSWA-AN-0001, D&D Work Plan for Building 064, Environmental Restoration
4. ER-AN-0002, ETEC Environmental Restoration Program Management Plan, dated October 25, 1991
5. N001OP000033, Methods and Procedures for Radiological Monitoring
6. N001OP000028, Quality Control and General Operating Procedure for Gamma Spectroscopy Using Canberra Multichannel Analyzers
7. DOE Order 5400.5, Radiation Protection of the Public and the Environment, dated February 8, 1990
8. DECON-1, State of California Guidelines for Decontaminating Facilities and Equipment Prior to Release for Unrestricted Use, dated June 1977
9. NRC Dismantling Order for the L-85 Reactor Decommissioning, NRC to M. E. Remley, dated March 1, 1983
10. DOE/CH/8901, A Manual for Implementing Residual Radioactive Material Guidelines, T. L. Gilbert, et al., June 1989
11. MIL-STD-414, Sampling Procedures and Tables for Inspection by Variables for Percent Defective, June 11, 1957
12. N704SRR990035, Radiological Assessment of the Building T064 Fenced-In Yard, January 12, 1994
13. N704SRR990031, Final Decontamination and Radiological Survey of the Building T064 Side Yard, Rev. A, September 10, 1993
14. SSWA-AR-0002, Building 064 D&D Operations Final Report
15. SSWA-SP-0001, Building 064 Interior Final Survey Procedure (completed "on-site work copy") dated February 25, 1993

1.0 INTRODUCTION

Decontamination and decommissioning (D&D) of a number of formerly used nuclear facilities and sites is underway at Rockwell International's Santa Susana Field Laboratory (SSFL). During D&D of these facilities, reasonable efforts are being made to eliminate or to reduce residual radioactive contamination to levels that are as low as reasonably achievable (ALARA). Upon completion of D&D, radiological surveys are performed under established protocols to determine that any remaining radioactivity does not exceed applicable regulatory limits. Findings from the surveys are also used to perform additional D&D or radiological investigations, as needed. The scope of the surveys includes both known and suspected areas of contamination in the Building 064 interior.

In accordance with a broad radiological survey plan for the SSFL (Ref. 1), a comprehensive radiological survey of Building 064 and its surrounding area was performed in 1988 (Ref. 2). Results of that survey showed that the soil of the Side Yard was radioactively contaminated (which was subsequently cleaned [Ref. 13]) and that some items within the building and the ventilation exhaust filter plenums were contaminated. This report presents the final status survey results following removal of the contaminated items and the filter plenums, and removal of the floor tiles.

This report is organized as follows: first, the summary of the results of the survey and the conclusions and recommendations; second, the background information concerning past radiological status, D&D efforts, and current radiological status; third, the survey results and the technical approach used in the data collection, analyses, and limit criteria; and fourth, the supporting documentation and calculations for historical records and report completeness.

2.0 SUMMARY AND CONCLUSIONS

Survey measurements were made for surface contamination (alpha and beta) on the interior walls, floors, and ceilings in Building 064, and for ambient gamma exposure rate at 1 meter above the interior floors. These measurements were tested statistically for compliance with acceptable contamination limits for enriched uranium, activation products, and mixed fission products, and for ambient exposure rate.

All tests for surface contamination showed that the facility is suitable for release without radiological restrictions. Interpretation of the gamma exposure rate measurements for the Building 064 interior is based on the average gamma exposure rate background value (15.76 $\mu\text{R/hr}$) for a building of similar construction (Building S445) that

has never been used for any radiological purposes. The probability distributions of the comparisons between these measurements shows no local contamination, except for two measurements that were affected by the near proximity of smoke alarm units containing approximately 80 μCi Am-241. The results indicate a natural/normal background distribution for the building, with an average value of 14.7 $\mu\text{R/hr}$. Therefore, the Building 064 interior average gamma exposure rate is consistent with the average gamma exposure rate for Building S445.

3.0 BACKGROUND

3.1 Location

Building 064 is located within Rockwell International's SSFL in the Simi Hills of southeastern Ventura County, California, adjacent to the Los Angeles County line and approximately 29 miles northwest of downtown Los Angeles, directly south of the City of Simi Valley. Location of the SSFL relative to Los Angeles and vicinities is shown in Figure 1. An enlarged map of neighboring SSFL communities is shown in Figure 2. Figure 3 is a plot plan of the western portion of SSFL known as Area IV, where Building 064 is located. Building 064 is located on government-optioned land, subject to the Health and Safety Clause of the operating contract with DOE, and is exempt from licensing.

3.2 Topography and Building Characteristics

Building T064 was designed and built as a special nuclear material and source radioactive material storage building. It was constructed in two phases. The first phase was constructed in 1958. This 2137 ft^2 portion, (room 110), is a reinforced concrete structure with 11-in thick walls on a concrete slab. The building eave height is 16 ft, and the structure is open bay except for a 12 ft x 13 ft material handling area in the southeast corner of the building. A fume hood was installed in this small southeast corner, (room 104).

In 1963, the building was enlarged by adding a bay to the north (room 114) bringing the total square footage of the building to 4418 ft^2 . This addition used 12-in concrete block construction with cores filled with concrete. Total square footage includes a small 150 ft^2 office (room 100) and a 50 ft^2 rest room (room 102), both located on the dock on the east side of the building. On the northwest corner is a small supply and storage room, about 50 ft^2 , (room 116).



Figure 1. Location of SSFL in relation to Los Angeles and Vicinity



Figure 2. Map of Neighboring SSFL Communities



The concrete-slab floors were covered with 12-in square vinyl-asbestos tiles. The concrete-block walls are painted. In 1980, the entire facility was reroofed; interior wall surfaces were patched and painted; floor tile was removed and replaced; the rest room and office were restored; asphalt was patched; plumbing was repaired; heating and ventilation was repaired; and a window air-conditioner was installed in the office. Ten-ft-long fluorescent lights were suspended from the 16-ft high ceiling. Storage racks were constructed to accommodate fuel. Room 114 is accessible from the east through a 20 ft x 15 ft electrically driven rollup door and a conventional hinged door. Room 110 is accessible from the east through a heavy secured door. These two rooms are extremely secure. Ramps leading to each room allow easy transport of materials via forklift.

Since nuclear material was only stored here, there was no processing equipment within the building. No sinks were installed in the storage areas. The only water supply was to the rest room (room 102); this water was released to the sewer. The facility is not air conditioned. Each vault was ventilated by dedicated blowers through a plenum containing pre-filters and HEPA filters. Room 104 had a fume hood which exhausted through the south filter plenum.

Figure 4 is a plot plan of the building and immediate surrounding yard area. The facility sits atop a plateau about 25 ft above "G" Street and slightly above the 513 parking lot. Rock outcroppings exist upslope to the north-northeast and downslope in every other direction. Water runoff is primarily due east at the southern end of the facility. A sanitary leach field existed several years ago just north of the access road to "G" Street on the southeast section of the property. The building is surrounded by a chain link fence which is located from 20 to 30 ft from the exterior walls of the building. The area it encloses, including the building, is about 11,000 ft².

There are three points of access to the site location of Building T064. One access is directly from the north through the 513 parking area which is on the east side of 10th Street. A second point of access is directly off 10th Street at the NW corner of the facility, and the third is a short paved roadway connecting the SE corner of the facility with "G" Street to the east. There are two gates for accessing the fenced-in storage yard. One from the northeast corner, off of the 513 parking lot. The other from the southeast corner, off of "G" Street. Figure 5 is an aerial photo of Building T064 as viewed from the east side of the facility including the dock, office, crane, and main entrance.




Figure 4. Building 064 Plan View




Figure 5: Aerial Photograph of Building 064, Viewing Eastside

3.3 Operating History

This building was used primarily for storage of packaged items of source material (normal uranium, depleted uranium, thorium) and special nuclear material (enriched uranium, plutonium, U-233) of various forms and configurations. Originally both the north (room 114) and the south (room 110) vaults contained steel racks for storing material. The south side was primarily used for storage of highly enriched uranium and plutonium bearing items; the north side was primarily used for source material and low enriched uranium storage.

Enriched uranium powders and source material powder packages were split into smaller units or combined into larger units in a glove box located in the small work area alcove (room 104) in the southeast corner of room 110. The glove box has since been removed from the building. Plutonium was handled only in packaged form; never in a loose form. No plutonium repackaging was done other than transferring sealed packages between containers. Transfers of solid metallic forms of material generally were handled in the glove box; however, on occasion, larger pieces were transferred and repackaged within the vault area. During shutdown and termination of the SNAP program, excess Zr-U (enriched U) alloy product line material was sectioned into lengths suitable for packaging for shipment in DOE (AEC) containers. This was done near the edge of the south side alcove in the vault. The floor was covered with plastic sheets before the Zr-U was sectioned using a common hack saw.

During the early 1960's, a changed storage configuration was required. The metal racks from the south half of room 110 was removed in order to store material in "birdcages" and drums. This storage included large quantities of special nuclear material recoverable scrap.

During this time, recoverable scrap space was at a premium. As a result, the entire yard area in front of the building (East), the side (North) and the back (West) was filled with 55 gallon drums of low enriched recoverable scrap. This material was shipped to various recovery sites in the mid-to late 1960's and early 1970's.

No plutonium or U-233 packages were ever opened in either vault. Any residual radioactive contamination is enriched uranium, normal uranium, depleted uranium, or thorium and generally could be expected to have come from "dust" from handling bare metallic pieces.

During the mid 1970's to early 1980's, most of the major DOE nuclear development and reactor contracts had ended.

No special nuclear material powders were handled or repackaged after 1980. Most of the material had been sent to other DOE sites for recovery and use. A new roof was installed on the facility in 1980 to correct leaks. Shortly afterward, the walls were repainted and other repairs were made. The racks from the north vault were removed and the area converted to storage of non-nuclear DOE components.

No reports of contamination incidents occurring within the building were recorded in the overall incident file.

3.4 Decommissioning and Demolition Efforts

To release the facility for use without radiological restrictions, all contaminated equipment and fixtures had to be removed in preparation for the final radiological survey. In addition, all hazardous materials and wastes in the facility had to be properly disposed. Where practical and cost effective, equipment was decontaminated and either disposed as non-RA waste or surplus. Some equipment required disassembly in order to remove hazardous materials such as oils, grease, and lead. Most of the items, however, could not be readily decontaminated and some equipment had areas that could not be surveyed with the confidence level necessary for release without radiological restrictions. Analysis of the floor tiles indicated that the tiles and mastic glue throughout the facility contained asbestos and would require removal and disposal.

The decommissioning work performed in room 114 consisted of the removal of miscellaneous packaged components and approximately 195 cubic yards of previously packaged containerized soil temporarily stored there. All of the items stored in room 114 were brought to the facility for storage after work with nuclear materials had ceased at B/064 and had been properly packaged to prevent release of contamination. During the removal of the equipment and boxes of soil, frequent area contamination surveys were performed by Radiation Protection and Health Physics Services (RP&HPS) representatives to assure that container integrity and contamination control were maintained. All contaminated equipment, components, and soil that had been stored in room 114 were transported to the RMDF for temporary storage awaiting eventual disposal at an approved DOE burial site.

Most of the items in room 110 had been used for operations at B/064 and were contaminated to varying degrees. When practical, size reduction and packaging were performed in the facility. However, some of the equipment required more aggressive techniques for size reduction and contamination control. These items included: a fume hood that had been

used to package enriched uranium powders and source materials, two large balances, and several steel shipping drum inserts. All of these items were transferred to the RMDF for size reduction and packaging for disposal. The fluorescent light fixtures in this room were found to be contaminated and were taken down, disassembled, and the PCB containing ballasts were removed. The fixtures (less ballasts and bulbs) were packaged and disposed of as radioactive waste. The ballasts were surveyed and found to be radiologically clean and were disposed of as hazardous PCB waste. The fluorescent bulbs were decontaminated and disposed of as conventional waste. The storage racks contained fixed RA contamination and were disassembled, size reduced, and packaged, and transferred to the RMDF for eventual shipment to an approved disposal facility.

To maintain contamination control during the size reduction of the HEPA filter plenums, size reduction was done at the RMDF. The plenums were detached from the buildings and blowers as intact units and transported to the RMDF. Because of the large size of the exhaust plenums, this effort required the fabrication of custom boxes to assure contamination control during transport. Inlet and outlet openings were sealed, the units were disconnected from the building, placed in the boxes and transferred to the RMDF. The plenums were cut into manageable pieces using a plasma torch and packaged for disposal as radioactive waste.

Because the facility had been used for storage for a number of years, special attention was given to identifying hazardous or potentially hazardous materials requiring disposition. Two scales were found to contain oil and one also contained lead. A four-ounce quantity of oil from one of the scales was determined to contain radioactive contamination and was effectively treated during the Molten Salt Oxidation (MSO) Bench Scale Unit tests being performed at the RMDF. The other oil and the lead were certified as "Containing No DOE-Added Radioactivity," in accordance with ER-SP-0001 and were disposed of in accordance with the Rocketdyne Environmental Control Manual. The ballasts removed from the light fixtures in room 110 were hermetically sealed units and after a thorough radiological survey were also certified as "Containing No DOE-Added Radioactivity" and were disposed of in accordance with the Rocketdyne Environmental Control Manual.

Because the tiles throughout the facility had been determined to contain asbestos and were in a deteriorated state their removal was required. A sampling plan was developed and implemented in accordance with ER-SP-0001. Randomly selected tiles were removed and the tiles and subfloor were surveyed for total contamination. The results of this survey sampling concluded that the tiles

and subfloor had no detectable activity (NDA) above background; therefore, all tiles were certified as "Containing No DOE-Added Radioactivity." An asbestos abatement contractor was employed to remove a total of 4,352 ft² of tile. The tile and abatement-related ACM wastes have been packaged and placed in an approved hazardous waste container and will be disposed at an approved disposal facility. Copies of certifications were forwarded to the DOE.

4.0 SURVEY RESULTS

4.1 Overview

Upon D&D of radioactive constituents, releasing a facility or area for unrestricted use requires a formal radiation survey to demonstrate that the applicable regulatory limits for such a release are met. The survey is performed under an established plan, and a statistical interpretation of the resulting data is made to determine if the regulatory release criteria have been met. This document provides information that demonstrates that Building 064 meets DOE, NRC, and State of California criteria for release of the facility for unrestricted use.

4.2 Scope of the Survey

For the final radiological survey of Building 064, the interior rooms and office were separated into sample lots. These sample lots are graphically shown in Figure 6. Sample lots were treated separately for the purposes of statistical data analyses. Distinguishable properties for selecting the sample lots were areas or rooms which contained contaminated components that were recently decontaminated. The chosen sample lots or areas are shown in Table 1 with the corresponding type of survey performed. (The Fenced-In Yard has been surveyed and reported [Ref. 12]. The Side Yard, to the east, has also been surveyed and reported [Ref. 13]).

Table 1. Sample Lots Surveyed

Sample Lot No.	Room or Area	Type of Survey Performed ^(1,3)				
		Total		Removable		Ambient Gamma ⁽²⁾
		Alpha	Beta	Alpha	Beta	
1	Rooms 110 & 104	x	x	x	x	x
2	Room 114	x	x	x	x	x
3	Rooms 116, 120, & rest rooms	x	x	x	x	x

- (1) The type of survey performed for each sample lot was dependent on the type of surface being measured (e.g., concrete floor, walls, asphalt, gravel roof, tile floors, etc.)
- (2) Ambient gamma readings are performed only on the horizontal walking surfaces at 1 meter.
- (3) 20% of all structural surfaces were surveyed in each sample lot for total alpha, total beta, removable alpha, and removable beta.




Figure 6: Building 064 Interior Sample Lot Identification

4.3 Survey Methods

The survey methods used for Building 064 interior are described in detail in Ref. 15. Maps, diagrams, and raw data for the final survey are also found in Ref. 15. Described below is a summary of those methods.

1. Sampling Method

The method and type of survey measurements depended on the type of surfaces involved. For each sample lot, a 3-meter by 3-meter grid was superimposed on the floors, walls, ceilings, or ground of the entire sample lot area. A 100% direct frisk of each 3-m by 3-m grid was then performed using a G-M pancake probe. A 1-meter by 1-meter area was then selected from each 3-m by 3-m area based on previous D&D knowledge, randomly, or indications of elevated readings from the 100% direct frisk.

Each selected 1-m by 1-m grid location was then surveyed for contamination based on the type of surface involved. This method satisfies the State of California guidelines in DECON-1 (Ref. 8) for a minimum of 10% of an area shall be surveyed, and is shown graphically in Figure 7. Walls, floors, and ceilings were surveyed for total alpha and beta activity, removable alpha and beta activity and maximum alpha and beta activity, if a "hot spot" was detected when the total alpha and beta measurements were made. Additionally, the floors were surveyed for ambient gamma exposure rate in $\mu\text{R/hr}$ at 1 meter above the floor. Twenty percent of all structural surfaces (pipes, conduit, light fixtures, etc.) were surveyed for total and removable alpha and beta activity. Concrete slabs and pads were surveyed in the same manner as the interior floors. (Asphalt paving around the building was surveyed in another project and was reported in Ref. 12).

2. Instrument Calibrations and Checks

Measurements of the total and maximum alpha surface activities were made with alpha scintillation detectors, sensitive only to alpha particles with energies exceeding about 1.5 MeV. The detectors were calibrated with a Th-230 alpha source standard, traceable to NIST. A 5-min integrated count time was used.

Measurements of the total and maximum beta surface activities were made with a thin-window pancake Geiger-Mueller tube. The detectors were calibrated with a Tc-99 beta source standard, traceable to NIST. A 5-min integrated count time was used.

01/14/94




Figure 7: Typical Room or Area 3-Meter by 3-Meter Grid Markings

Measurements of removable surface activity (alpha and beta) were made by wiping approximately 100 cm² of surface area using standard smear disks. The activity on the disks were measured using a low-background gas-flow proportional counter. The counters were calibrated using Th-230 and Tc-99 standard sources, traceable to NIST. A 1-min integrated count time was used.

The ambient exposure rates at 1 m from surfaces were measured using a 1-in. NaI scintillation detector. These instruments were calibrated against a Reuter-Stokes high-pressure ionization chamber with natural background, and daily checks were made using a Ra-226 source, traceable to NIST, placed 1-m from the detector. A 1-min integrated count time was used.

All portable survey instruments were serviced and calibrated with NIST traceable standards on a quarterly basis. In addition, daily (when used) checks and calibrations were performed on all instrumentation to determine acceptable performance and establish a background value for the instrument on that day. Reference 5 provides further methods and procedures for environmental surveys.

Soil analyses were performed using a high purity Ge detector gamma-spectroscopy system calibrated with a NIST traceable standard. Reference 6 contains additional information concerning the entire method by which soil analyses are validated.

4.4 Technical Approach

1. Criteria and Their Implementation

Acceptable contamination limits and gamma exposure rates for releasing a facility for unrestricted use are prescribed in DOE guidelines (Ref. 7). The lowest (most conservative) limits were chosen from these guidelines and incorporated into the final survey criteria for Building 064. Two distinguishable criteria were chosen from the guidelines.

- a) The surface contamination limits for alpha and beta were excerpted from DOE Order 5400.5 (Ref. 7 and State of California guidelines (Ref. 8));

- b) The ambient gamma exposure rate limits at 1 m were excerpted from NRC Dismantling Order for the L-85 reactor decommissioning (Ref. 9) for conservatism and consistency with past decommissioning efforts. Although DOE Order 5400.5 (Ref. 7) recommends a value of 20 $\mu\text{R/hr}$ above background, the value of 5 $\mu\text{R/hr}$ from the NRC Dismantling Order (Ref. 9) was used for consistency, conservatism, and in keeping with ALARA principles.

Determination of an appropriate value for gamma exposure rate background has been a continuing problem, due to the variability of natural radiation on the site and differences between indoors and out. Reference values that have been used are 8.10 $\mu\text{R/hr}$ inside a steel-walled and -roofed building with plasterboard office walls, and from 14.0 to 16.6 $\mu\text{R/hr}$ in outside areas. This building does not correspond to either case, being an empty concrete structure.

To resolve this difficulty, a building with similar construction was sought for the purpose of determining a comparable radiation background. Building S445, near the entrance to SSFL and never used for nuclear or radioactive materials, was selected. This building was a concrete slab floor, cast-in-place concrete walls up to about 3 ft above grade with concrete blocks above, and a poured concrete roof. The ambient gamma exposure rate was measured, in the same manner as for a final survey, at 40 locations within Building 445, on an evenly spaced 1-m grid. A cumulative probability plot of these measurements is shown in Figure 8. This shows that the majority of values, with the exception of one anomalously low measurement, fit a Gaussian distribution very well. (The low value was measured adjacent to the steel double doors of the building, one open, the other closed.) The average of these values is 15.76 $\mu\text{R/hr}$, and the acceptance limit for gamma exposure rate in buildings of this sort is 20.76 $\mu\text{R/hr}$.

Table 2 provides a summary of the contamination limit criteria. Table 3 demonstrates that the detection limits (SSAs) for the instruments and method are well below the established limit criteria (from regulatory requirements) shown in Table 2.

01/14/94

01-31-94

bldgbkg.csv

Building 445 Gamma Exposure Rate




Figure 8: Gamma exposure rate measured in Bldg. 445. Concrete building (Bldg. 445) has construction similar to that of T064 and no radiological history. Confidence bounds (95%) on least-squares fit of data are close to the derived Gaussian line. One value is anomalously low due to measurement near doorway. See Appendix B for data measurements.

Table 2. Building 064 Contamination Limit Criteria

Parameter	Limit				Reference
	Radionuclides ⁽²⁾	Average ^(3,4)	Maximum ^(4,5)	Removable ^(4,6)	
Allowable Total					
Residual surface contamination for alpha and beta (dpm/100-cm ²) ⁽¹⁾	U-natural, U-235, U-238, & associated decay product, alpha emitters	≤5,000	≤15,000	≤1,000	8,9
Gamma exposure rate	≤5 μR/hr above background at 1 m interior				10

¹ As used in this table, dpm (disintegrations per minute) means the rate of emission by radioactive material as determined by correcting the counts per minute measured by an appropriate detector for background, efficiency, and geometric factors associated with the instrumentation.

² Where surface contamination by both alpha- and beta-gamma-emitting radionuclides exists, the limits established for alpha- and beta-gamma-emitting radionuclides should apply independently.

³ Measurements of average contamination should not be averaged over an area of more than 1 m². For objects of less surface area, the average should be derived for each such object.

⁴ The average and maximum dose rates associated with surface contamination resulting from beta-gamma emitters should not exceed 0.2 mrad/h and 1.0 mrad/h, respectively, at 1 cm.

⁵ The maximum contamination level applies to an area of not more than 100 cm².

⁶ The amount of removable material per 100 cm² of surface area should be determined by wiping an area of that size with dry filter or soft absorbent paper, applying moderate pressure, and measuring the amount of radioactive material on the wiping with an appropriate instrument of known efficiency. When removable contamination on objects of surface area less than 100 cm² is determined, the activity per unit area should be based on the actual area and the entire surface should be wiped. It is not necessary to use wiping techniques to measure removable contamination levels if direct scan surveys indicate that the total residual surface contamination levels are within the limits for removable contamination.

Table 3. Observed Detection Limits versus Established Limit Criteria

	Total Alpha (dpm/100 cm ²)	Removable Alpha (dpm/100 cm ²)	Total Beta (dpm/100 cm ²)	Removable Beta (dpm/100 cm ²)	Ambient Gamma Exposure Rate (μR/hr)
Limit criteria	5000	1000	5000	1000	<5.0 above background
Average obs. detection limit (SSA*)	10	4	316	12	0.60
Obs. detection limit range	3-36	2-19	252-373	6-23	0.49-0.66
Ratio of ave-obs. detection limit to established limit criteria	0.20%	0.39%	6.32%	1.17%	12.02%

*SSA = 1.645 x SQRT (2 x counts) x area factor x efficiency factor/minutes = dpm/100 cm²

2. Data Analyses and Statistical Criteria

A statistical procedure was used to validate the applicability of the raw survey data for selected sample lots or areas. The statistical method known as "sampling inspection by variables" (Ref. 11) was used. This method has been widely applied in industry and the military and is essential where the lot size is impractically large. In the case of determining residual contamination in Building 064, it would be unacceptably time consuming and not cost effective to measure and document 100% of the building. However, by applying sampling inspection by variables methods, acceptable confidence in the conclusion made about the level of contamination can be achieved.

In sampling inspection by variables, the number of data points on which measurements are obtained is first chosen to be large so that the parameters of the distribution are likely to have a normal distribution (i.e., Gaussian). The mean of the distribution, \bar{x} , and its standard deviation, s , are then related to a "test statistic," TS , as follows:

$$TS = \bar{x} + ks$$

where \bar{x} = average (arithmetic mean of measured values)

s = observed sample standard deviation

k = tolerance factor calculated from the number of samples to achieve the desired sensitivity for the test

UL = acceptance limit

TS and \bar{x} are then compared with an acceptance limit, UL (such as those shown in Table 2), to determine acceptance or other plans of action, including rejection of the area as contaminated and requiring further remediation.

The sample mean, standard deviation, and acceptance limit are easily calculable quantities; the value of k , the tolerance factor, bears further discussion. Of the various criteria for selecting plans for acceptance sampling by variables, the most appropriate is the method of Lot Tolerance Percent Defective (LTPD), also referred to as the Rejectable Quality Level (RQL). The LTPD is defined as the poorest quality that should be accepted in an individual lot. Associated with the LTPD is a parameter referred to as consumer's risk (β), the

risk of accepting a lot of quality equal to the LTPD. USNRC Regulatory Guide 6.6 ("Acceptance Sampling Procedures for Exempted and Generally Licensed Items Containing By-Product Material") states that the value for the consumer's risk should be 0.10. Conventionally, the value assigned to the LTPD has been 10%.

The State of California has stated that the consumer's risk of acceptance (β) at 10% defective (LTPD) must be 0.1. For those choices of β and LTPD, $K_\beta = K_2 = 1.282$. The number of samples is n . Values of k for each sample size are calculated in accordance with the following equations:

$$K = \frac{K_2 + \sqrt{K_2^2 - ab}}{a}; \quad a = 1 - \frac{K_\beta^2}{2(n-1)}; \quad b = K_2^2 - \frac{K_\beta^2}{n} \quad (Eq.1)$$

where k = tolerance factor

K_2 = the normal deviate exceeded with probability of β , 0.10 (from tables, $K = 1.282$)¹

K_β = the normal deviate exceeded with probability equal to the LTPD, 10% (from tables, $K = 1.282$)¹

n = number of samples

The statistical criteria for acceptance of the Building 064 interior final survey are presented below.

- a) Acceptance: If the test statistic ($\bar{x} + ks$) is less than or equal to the limit (UL), accept the region as clean. (If any single measured value exceeds 80% of the limit, decontaminate that location to as near background as is possible, but do not change the value in the analysis.) See Figure 9 for an example of the sample lot acceptance by the test.

¹The values chosen for these coefficients for the survey correspond to assuring, with 90% confidence, that 90% of the area has residual contamination below 100% of the applicable limit (a 90/90/100 test). The choice of values for the two coefficients is consistent with industrial sampling practices and State of California guidelines (Ref. 8).

01/14/94




Figure 9. Example of Sample Lot Acceptance, where $TS(=\bar{x}+ks) \leq UL$ and $\bar{x} \leq UL$




Figure 10. Example of Sample Lot Requiring Additional Measurements, where $TS(=\bar{x}+ks) > UL$ and $\bar{x} < UL$

- b) Collect additional measurements: If the test statistic ($\bar{x} + ks$) is greater than the limit (UL), but \bar{x} itself is less than UL, independently resample and combine all measured values to determine if $\bar{x} + ks \leq UL$ for the combined set; if so, accept the region as clean. If not, the region is contaminated and must be remediated. See Figure 10 for an example of additional measurements that must be taken in the sample lot to accept or reject it.
- c) Rejection: If the test statistic ($\bar{x} + ks$) is greater than the limit (UL) and $\bar{x} > UL$, the region is contaminated and must be remediated. See Figure 11 for an example of sample lot rejection by the test.

Thus, based on sampling inspection, we are willing to accept the hypothesis that the probability of accepting a lot as not being contaminated which is, in fact, 10% defective is 0.10. Or in other words, the Building 064 final survey corresponds to assuring with 90% confidence that 90% of the area has residual contamination below 100% (a 90/90/100 test) of the applicable limits described in Table 2.

4.5 Sample Lot Analyses and Results

1. Sample Lot 1

a) Description

Sample Lot 1 consists of room 110 and the southern section of the building, and room 114, where the fume hood had been installed.

b) Analyses of Sample Lot 1 Data

Raw data measurements for Sample Lot 1 were taken, subtracted for daily instrument background (except for ambient gamma exposure rates) and plotted on a cumulative probability graph as explained previously. For statistical comparisons (using the "sampling inspection by variables" method), similar areas within Sample Lot 1 were combined together and then analyzed for the specific type of radiation measurement made on the surface. Individual raw measurement data and instrument backgrounds are provided in Appendix A.

01/14/94




Figure 11. Example of Sample Lot Rejection, where $TS(=\bar{X}+ks) > UL$ and $\bar{X} > UL$

01/14/94

Table 4. Sample Lot 1 Results

	Calculated Test Statistic (TS = \bar{x} + ks)				
	Total		Removable		Gamma Exposure Rate (μ R/hr @ 1 m)
	Alpha (dpm/100 cm ²)	Beta (dpm/100 cm ²)	Alpha (dpm/100 cm ²)	Beta (dpm/100 cm ²)	
Acceptance Limit (UL)	5000	5000	1000	1000	20.76**
Floors only					16.25 (16)*
Entire area - floors, walls, ceiling, & structure	74.77 (12)*	863.5 (14)*	6.29 (13)*	12.98 (15)*	

* Numbers in parenthesis refer to figure numbers.

** The acceptance limit for ambient gamma exposure rate in μ R/hr was determined by calculating the average ambient indoor background (15.76 μ R/hr) from 40 locations inside a known uncontaminated building (Bldg. S445) and adding the acceptance criteria from Table 2 (<5 μ R/hr above background) to achieve a final indoor ambient gamma exposure rate limit of 20.76 μ R/hr. All values, excluding the ambient gamma exposure rate, in this table are subtracted for daily instrument background.

Sample lot results are summarized in Table 4 for comparing the test statistic ($TS = \bar{X} + ks$) with applicable, established contamination criteria or acceptance limit (UL) from Table 2. The corresponding figures for the graphs of each calculated cumulative probability plot are also provided. Individual sample results used as graph data for Sample Lot 1 are provided in Appendix B.


Initial review of the gamma exposure rate data, by use of the cumulative probability plot, showed an apparent discrepant value of $17.54 \mu R/hr$ at floor grid location 5,12. On investigation, it was found that a wall-mounted smoke alarm unit was approximately 1 meter away from the gamma detector during the measurement.

The radioactive source contained in this unit produces an estimated exposure rate of $2.79 \mu R/hr$ at the detector location. In the statistical interpretation of the Lot 1 data, this measurement has been reduced from 17.54 to $14.75 \mu R/hr$ to correct for this effect. The uncorrected value is listed in the appendix of survey results. (A similar smoke alarm unit is mounted on the wall of room 114 [Lot 2] but no adjacent measurements were made and so no corrections were required. An additional 6 units were mounted on each of the ceilings of rooms 110 and 114 and one unit in room 116, but increase the ambient exposure rate by only about $0.5 \mu R/hr$.)


c) Interpretation of Results for Sample Lot 1

Figures 12 through 16 and Table 4 demonstrate that for each applicable acceptance limit (UL) from Table 2, the corresponding test statistic (TS) value is less than the UL or $TS < UL$. Therefore, the nine figures for Sample Lot 1 pass the "sampling inspection by variables" test and are "Accepted" as radiologically clean. Or in other words, the Building 064 Sample Lot 1 survey corresponds to assuring with a 90% confidence that 90% of Sample Lot 1 has residual contamination below 100% (a 90/90/100 test) of the applicable NRC, DOE, and State of California limits described in Table 2.

01/14/94




12a.) Scale including Acceptance Limit (UL)




12b.) Expanded Scale

Figure 12: T064 - LOT 1 Total Alpha Activity

01/14/94




13a.) Scale including Acceptance Limit (UL)




13b.) Expanded Scale

Figure 13: T064 - LOT 1 Removable Alpha Activity

01/14/94




14a.) Scale including Acceptance Limit (UL)




14b.) Expanded Scale

Figure 14: T064 - LOT 1 Total Beta Activity




15a.) Scale including Acceptance Limit (UL)



15b.) Expanded Scale

Figure 15: T064 - LOT 1 Removable Beta Activity



16) Scale including Acceptance Limit (UL)

Figure 16: T064 - LOT 1 Floors Ambient Gamma Exposure Rate

2. Sample Lot 2

a) Description

Sample Lot 2 consists of room 114, the northern section of the building.

b) Analyses of Sample Lot 2 Data

Raw data measurements for Sample Lot 2 were taken, subtracted for daily instrument background (except for ambient gamma exposure rates) and plotted on a cumulative probability graph as explained previously. For statistical comparisons (using the "sampling inspection by variables" method), similar areas within Sample Lot 2 were combined together and then analyzed for the specific type of radiation measurement made on the surface. Individual raw measurement data and instrument backgrounds are provided in Appendix A. (The "total beta" measurements for two wall grid locations in room 110 were lost, and were replaced by measurements made in January 1994 to provide a complete set of data.)

Sample lot results are tabulated in Table 5 for comparing the test statistic ($TS = \bar{x} + ks$) with applicable, established contamination criteria or acceptance limit (UL) from Table 2. The corresponding figures for the graphs of each calculated cumulative probability plot are also provided. Individual sample results used as graph data for Sample Lot 2 are provided in Appendix B.

01/14/94

Table 5. Sample Lot 2 Results

	Calculated Test Statistic (TS = \bar{x} + ks)				
	Total		Removable		Gamma Exposure Rate (μ R/hr @ 1 m)
	Alpha (dpm/100 cm ²)	Beta (dpm/100 cm ²)	Alpha (dpm/100 cm ²)	Beta (dpm/100 cm ²)	
Acceptance Limit (UL)	5000	5000	1000	1000	20.76**
Floors only					16.0 (21)*
Entire area - floors, walls, ceiling, & structure	5.51 (17)*	938.7 (19)*	1.033 (18)*	9.067 (20)*	

* Numbers in parenthesis refer to figure numbers.

** The acceptance limit for ambient gamma exposure rate in μ R/hr was determined by calculating the average ambient indoor background (15.76 μ R/hr) from 40 locations inside a known uncontaminated building (Bldg. S445) and adding the acceptance criteria from Table 2 (<5 μ R/hr above background) to achieve a final indoor ambient gamma exposure rate limit of 20.76 μ R/hr. All values, excluding the ambient gamma exposure rate, in this table are subtracted for daily instrument background.

c) Interpretation of Results for Sample Lot 2

Figures 17 through 21 and Table 4 demonstrate that for each applicable acceptance limit (UL) from Table 2, the corresponding test statistic (TS) value is less than the UL or $TS < UL$. Therefore, the nine figures for Sample Lot 2 pass the "sampling inspection by variables" test and are "Accepted" as radiologically clean. Or in other words, the Building 064 Sample Lot 2 survey corresponds to assuring with a 90% confidence that 90% of Sample Lot 2 has residual contamination below 100% (a 90/90/100 test) of the applicable NRC, DOE, and State of California limits described in Table 2.

3. Sample Lot 3

a) Description

Sample Lot 3 consists of the office (room 120) and rest room, and the storage closet, room 116.


b) Analyses of Sample Lot 3 Data

Raw data measurements for Sample Lot 3 were taken, subtracted for daily instrument background (except for ambient gamma exposure rates) and plotted on a cumulative probability graph as explained previously. For statistical comparisons (using the "sampling inspection by variables" method), similar areas within Sample Lot 3 were combined together and then analyzed for the specific type of radiation measurement made on the surface. Individual raw measurement data and instrument backgrounds are provided in Appendix A.


Sample lot results are tabulated in Table 6 for comparing the test statistic ($TS = \bar{x} + ks$) with applicable, established contamination criteria or acceptance limit (UL) from Table 2. The corresponding figures for the graphs of each calculated cumulative probability plot are also provided. Individual sample results used as graph data for Sample Lot 3 are provided in Appendix B.

This lot also showed an outlier in the gamma exposure rate data. As in Lot 1, this elevated value was due to the close proximity of a smoke alarm unit. The measured value, 17.32 $\mu R/hr$, was reduced by 2.79 $\mu R/hr$ to 14.53 $\mu R/hr$ for statistical interpretation. The original measured value has been left in the tabulational results.

01/14/94




17a.) Scale including Acceptance Limit (UL)




17b.) Expanded Scale

Figure 17: T064 - LOT 2 Total Alpha Activity

01/14/94




18a.) Scale including Acceptance Limit (UL)




18b.) Expanded Scale

Figure 18: T064 - LOT 2 Removable Alpha Activity

01/14/94




19a.) Scale including Acceptance Limit (UL)




19b.) Expanded Scale

Figure 19: T064 - LOT 2 Total Beta Activity




20a.) Scale including Acceptance Limit (UL)



20b.) Expanded Scale


Figure 20: T064 - LOT 2 Removable Beta Activity

01/14/94




21) Scale including Acceptance Limit (UL)

Figure 21: T064 - LOT 2 Floors Ambient Gamma Exposure Rate




22a.) Scale including Acceptance Limit (UL)




22b.) Expanded Scale

Figure 22: T064 - LOT 3 Total Alpha Activity

01/14/94




23a.) Scale including Acceptance Limit (UL)




23b.) Expanded Scale

Figure 23: T064 - LOT 3 Removable Alpha Activity




24a.) Scale including Acceptance Limit (UL)




24b.) Expanded Scale

Figure 24: T064 - LOT 3 Total Beta Activity




25a.) Scale including Acceptance Limit (UL)



25b.) Expanded Scale

Figure 25: T064 - LOT 3 Removable Beta Activity



26) Scale including Acceptance Limit (UL)

Figure 26: T064 - LOT 3 Floors Ambient Gamma Exposure Rate

4. Supplemental Measurements

In addition to the standard survey measurements, several supplemental measurements were made to provide additional assurance of the quality of the decontamination effort. Special samples of paint from the walls were analyzed in gamma spectrometry. The detected activities are shown below:

	Cs-137	U-234	U-235
Paint (Lot 1)	0.1 dpm/100cm ²	1.6 dpm/100cm ²	0.3 dpm/100cm ²
Paint (Lot 2)	2.0 dpm/100cm ²	1.6 dpm/100cm ²	0.3 dpm/100cm ²
Paint (Lot 3)	0.4 dpm/100cm ²	1.5 dpm/100cm ²	0.1 dpm/100cm ²

All values are below the applicable limits and in agreement with the measurements for removable alpha and beta measurements results from the smears.

APPENDIX A

Building 064 Interior

Lots 1 through 3

Final Survey Data

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 1

Page 1 of 3

			GROSS COUNTS IN 5 MINUTES					In 1 MIN		ALPHA					BETA				GAMMA
SAMPLE	GRID		ALPHA			BETA		GAMMA		INSTRUMENT		SMEAR			INSTRUMENT		SMEAR		
NAME	NAME	TOTAL	MAX	REM	TOTAL	MAX	REM	TOTAL	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	AFACT	BACKG	EFACT	EFACT
Floors - Rms 104 & 110	1,1	7		0	358		0	3148	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	1,11	8		0	394		6	3207	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	2,6	4		0	427		9	3258	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	3,9	7		0	370		3	3217	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	4,7	5		0	400		2	3103	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	5,4	9		0	435		5	3116	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	5,12	10		1	412		2	3773	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	6,5	5		0	406		5	3087	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	7,2	2		0	410		2	3319	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	7,12	8		0	383		3	3094	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	8,8	5		0	393		2	3171	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	9,3	7		0	396		5	3171	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	10,6	3		0	392		7	3196	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	11,4	4		1	421		2	3219	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	12,7	3		0	382		5	3144	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	12,10	4		0	399		5	2973	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	13,5	4		0	387		3	3154	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	14,11	9		0	415		1	3106	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	14,2	7		0	358		6	3259	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Floors - Rms 104 & 110	15,5	5		0	392		4	2769	2.563	4.407	1.41	0.3	2.75	279.759	7.705	5	2.7	2.55	0.00465
Ceiling - Rms 104 & 110	1,5	4		0	272		2	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	2,8	2		0	289		4	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	3,12	6		0	334		8	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	3,2	3		0	289		4	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	4,6	2		1	287		8	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	5,9	4		0	287		6	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	6,4	5		0	274		3	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	6,11	4		0	289		2	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	7,1	9		0	320		5	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	8,3	5		0	272		7	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	9,7	4		0	299		2	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	9,12	8		1	304		1	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	10,5	4		0	305		4	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	11,2	5		0	319		5	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	11,11	3		0	299		2	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	12,9	4		1	287		7	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	13,2	6		6	322		5	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	14,3	4		1	326		4	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	
Ceiling - Rms 104 & 110	15,1	7		1	318		8	2167	4.445	1.41	0.3	2.75	272.333	7.648	5	2.7	2.55	0.00465	

T64L1DAT.WB1

SSWA-ZR-0001
Page 57
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 1

Page 2 of 3

SAMPLE NAME	GRID NAME	GROSS COUNTS IN 5 MINUTES		In 1 MIN		ALPHA		SMEAR		BETA		GAMMA	
		TOTAL	MAX	REM	TOTAL	MAX	REM	BACKG	EFACT	INSTRUMENT	AFAC	BACKG	EFACT
Ceiling - Rms 104 & 110	14.10	6		0	301		4	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	1.3	9		3	252		3	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	3.2	12		1	297		4	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	6.1	13		1	270		3	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	8.3	11		0	245		3	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	10.4	9		0	241		3	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	11.1	14		0	274		5	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	13.2	10		0	266		1	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 110	15.3	11		0	269		3	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	18.4	14		0	290		7	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	19.1	16		1	285		5	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	21.2	22		0	296		1	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	23.2	11		1	211		5	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	25.2	11		2	296		7	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 110	27.3	9		1	277		7	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 110	2.3	12		0	309		5	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 110	4.2	12		1	309		5	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 110	6.1	10		0	319		3	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 110	7-8.5	9		0	289		3	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 110	10.3	16		0	292		4	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	12.2	17		1	289		4	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	14.3	7		0	277		5	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	16.2	12		1	277		4	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	18.3	9		1	306		5	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	20.1	12		0	294		3	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	22.4	11		0	325		6	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 110	23.3	13		0	271		2	2.167	4.445	7.648	5	2.7	2.55
Wall East - Rm 104(deconned)	2.2	52	376	4	333	311	10	2.000	4.459	7.742	5	2.7	2.55
Wall East - Rm 104	4.2	12		1	307		5	2.167	4.445	7.648	5	2.7	2.55
Wall South - Rm 104(deconned)	5.1	13	227	1	301	284	1	2.000	4.459	7.742	5	2.7	2.55
Wall West - Rm 104	8.3	9		0	261		6	2.167	4.445	7.648	5	2.7	2.55
Wall West - Rm 104	10.1	35		9	280		15	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 104	12.3	12		0	298		3	2.167	4.445	7.648	5	2.7	2.55
Wall North - Rm 104	14.2-3	10		1	277		3	2.167	4.445	7.648	5	2.7	2.55
Structure - Trusses Rm 104	St-1	156		1	327		5	2.000	4.459	7.742	5	2.7	2.55
Structure - Trusses Rm 104	St-2	133		0	322		9	2.000	4.459	7.742	5	2.7	2.55
Structure - Trusses Exit Rm 110	St-3	48		3	228		2	2.000	4.459	7.742	5	2.7	2.55
Structure - Trusses NE corner Rm 110	St-4	80		0	325		1	2.000	4.459	7.742	5	2.7	2.55
Structure - Trusses near C(4,10)	St-5	48		1	319		3	2.000	4.459	7.742	5	2.7	2.55

T64L1DAT.WB1

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 1

Page 3 of 3

SAMPLE	GRID	GROSS COUNTS IN 5 MINUTES						In 1 MIN	ALPHA			BETA			GAMMA		
		ALPHA		BETA		GAMMA		INSTRUMENT	SMEAR		INSTRUMENT	SMEAR		INSTRUMENT	SMEAR		INSTRUMENT
		NAME	TOTAL	MAX	REM	TOTAL	MAX	REM	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	AFACT	BACKG
Structure - Trusses near Center	St-6		37		0	304		2	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Trusses C(6,4) near HTR	St-7		23		1	316		8	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Beam Ledges - West	Sb-1		77		2	256		3	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Beam Ledges - Center West	Sb-2		37		1	249		3	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Beam Ledges - Center	Sb-3		59		2	282		5	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Beam Ledges - Center East	Sb-4		111		0	288		4	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Beam Ledges - East	Sb-5		126		0	299		2	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Heater Outside Wall	Sh-1		6		0	266		2	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Heater Inside Grating	Sh-2		4		1	272		3	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7
Structure - Heater Inside Wall	Sh-3		2		0	239		5	2.000	4.459	1.41	0.3	2.75	268.833	7.742	5	2.7

T64L1DAT.WB1

SSWA-ZR-0001
Page 59
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 2

Page 1 of 2

					GROSS COUNTS IN 5 MINUTES						ALPHA					BETA			GAMMA		
SAMPLE	GRID		ALPHA			BETA			GAMMA		INSTRUMENT		SMEAR			INSTRUMENT		SMEAR			
NAME	NAME	TOTAL	MAX	REM	TOTAL	MAX	REM	TOTAL	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	
Floors - Rm 114	1,4	3		1	397		5	3294	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	2,1	2		0	402		4	3314	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	3,7	6		0	360		2	3172	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	2,10	0		0	391		4	3487	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	5,12	4		0	412		1	3373	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	4,5	7		0	383		7	2966	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	5,2	4		0	377		2	3110	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	6,6	3		0	394		6	3102	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	7,3	5		0	367		5	3120	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	8,8	2		0	413		3	3083	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	7,11	2		0	391		2	3192	2.563	4.407	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465	
Floors - Rm 114	9,4	6		0	393		6	3079	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	10,1	5		0	355		6	2932	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	11,7	7		0	382		6	2983	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	12,6	6		0	395		2	3017	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	12,10	6		1	335		4	3252	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	13,1	8		0	362		3	3047	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	14,5	7		0	369		2	3065	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	15,2	5		0	348		3	3010	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Floors - Rm 114	15,11	5		1	384		4	3481	3.167	4.394	1.41	0.3	2.75	293.167	7.775	5	2.7	2.55		0.00465	
Ceiling - Rm 114	1,1	4		0	268		5		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	2,4	6		1	256		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	3,6	4		0	229		7		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	4,3	5		0	252		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	5,2	6		0	275		5		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	6,6	1		1	236		4		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	7,7	8		0	224		1		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	8,9	3		0	238		5		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	9,4	6		1	256		4		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	10,5	7		0	248		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	11,9	4		0	246		4		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	12,2	6		0	246		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	13,4	4		1	227		4		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	14,7	5		0	277		7		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	15,6	2		1	248		3		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	13,12	7		0	265		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	10,10	6		0	238		4		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	8,12	4		0	267		3		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	
Ceiling - Rm 114	4,11	2		0	270		0		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465	

T64L2DAT.WB1

SSWA-ZR-0001
Page 60
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 2

Page 2 of 2

					GROSS COUNTS IN 5 MINUTES					ALPHA						BETA				GAMMA		
SAMPLE	GRID		ALPHA			BETA			GAMMA		INSTRUMENT		SMEAR			INSTRUMENT			SMEAR			
NAME	NAME	TOTAL	MAX	REM	TOTAL	MAX	REM	TOTAL	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT		
Celling - Rm 114	1,10	2		1	248		2		3.333	4.434	1.41	0.3	2.75	281.333	7.358	5	2.7	2.55		0.00465		
Wall - South Rm 114	3,1	5		0	311		5		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - South Rm 114	4,4	5		0	278		2		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - South Rm 114	5,2	3		0	276		7		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - South Rm 114	8,3	2		0	257		1		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - South Rm 114	8,5	2		0	257		3		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - South Rm 114	10,1	4		0	263		2		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - South Rm 114	11,4	4		0	283		1		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - South Rm 114	13,3	2		0	278		1		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - South Rm 114	15,5	3		0	293		3		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - West Rm 114	17,2	4		0	362		5		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - West Rm 114	20,2	4		0	370		2		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - West Rm 114	23,1	3		0	341		2		2.667	4.290	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - West Rm 114	26,3	3		0	339		6		2.667	4.290	1.41	0.3	2.75	287.833	7.808	5	2.7	2.55		0.00465		
Wall - West Rm 114	21,4	2		0	300		4		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - West Rm 114	25,4	3		0	349		3		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	2,2	5		0	368		6		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - North Rm 114	4,3	3		1	307		6		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	7,1	1		0	360		3		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - North Rm 114	10,3	2		0	318		3		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	13,1	1		1	358		2		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - North Rm 114	3,4	5		0	372		2		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	9,5	4		0	291		6		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	11,4	3		0	364		0		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - North Rm 114	15,4	6		0	319		2		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - East Rm 114	17,2	4		0	313		6		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - East Rm 114	20,2	2		0	323		1		2.167	4.379	1.41	0.3	2.75	274.833	7.995	5	2.7	2.55		0.00465		
Wall - East Rm 114	23,1	5		0	234		4		2.200	3.082	1.41	0.3	2.75	233.5	7.051	5	2.7	2.55		0.00465		
Wall - East Rm 114	26,1	3		0	315		3		2.167	4.379	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Wall - East Rm 114	19,1	8		0	376		5		2.200	3.082	1.41	0.3	2.75	233.5	7.051	5	2.7	2.55		0.00465		
Wall - East Rm 114	27,4	4		0	360		0		2.667	4.290	1.41	0.3	2.75	278.333	7.421	5	2.7	2.55		0.00465		
Structure - Trusses Rm 114 NW	St-1	4		0	242		3		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		
Structure - Trusses Rm114 Center	St-2	3		0	278		7		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		
Structure - Trusses Rm114 SE	St-3	5		0	280		4		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		
Structure - Beams Rm 114 North	Sb-1	8		0	263		3		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		
Structure - Beams Rm 114 Center	Sb-2	6		0	277		1		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		
Structure - Beams Rm 114 South	Sb-3	12		0	291		1		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465		

T64L2DAT.WB1

SSWA-ZR-0001
Page 61
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY DATA FOR LOT 3

Page 1 of 1

		GROSS COUNTS IN 5 MINUTES						1 MIN		ALPHA					BETA			GAMMA		
SAMPLE	GRID	ALPHA			BETA		GAMMA		INSTRUMENT		SMEAR			INSTRUMENT		SMEAR				
NAME	NAME	TOTAL	MAX	REM	TOTAL	MAX	REM	TOTAL	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT	AFACT	BACKG	EFACT	BACKG	EFACT
Floors - Rm 116	F-1	6		0	437		7	3725	2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Floors - Rm 116	F-2	45		0	432		7	2861	2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Ceiling - Rm 116	C-1	2		1	296		2		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Wall - West Rm 116	2,2	2		2	392		5		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Wall - North Rm 116	5,1	3		0	430		1		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Wall - East Rm 116	7,3	4		0	379		4		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Wall - South Rm 116	10,2	6		0	310		3		2.667	4.467	1.41	0.3	2.75	281.333	8.015	5	2.7	2.55		0.00465
Floors - Rm 120	3,1	8		0	378		2	2848	2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Floors - Rm 120	4,3	10		0	351		2	2414	2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Floors - Rm 120	7,3	25		0	352		3	2395	2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Floors - Rm 120	8,1	39		0	359		4	2038	2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Ceiling - Rm 120	1,4	5		0	244		3		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Ceiling - Rm 120	3,1	5		0	278		2		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall - West Rm 120	1,2	4		0	224		6		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall - West Rm 120	4,3	7		1	240		4		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall - East Rm 120	9,1	3		0	282		2		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall - East Rm 120	12,2	3		0	232		13		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall - South Rm 120	14,1	1		0	199		2		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Floors - Restroom	F-1	13		0	355		7	2200	2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Ceiling - Restroom	C-1	2		0	230		4		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall -West Restroom	3,2	12		0	252		1		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall -North Restroom	5,2	31		0	318		2		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465
Wall -East Restroom	7,1	2		0	281		6		2.333	4.393	1.41	0.3	2.75	279.833	7.579	5	2.7	2.55		0.00465

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 1

Page 1 of 3

SAMPLE NAME	GRID NAME	ALPHA (DPM/100CM2)								BETA (DPM/100CM2)				GAMMA (uR/hr)	
		TOTAL	STD DEV	MAX		REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV
Floors - Rms 104 & 110	1,1	5.52	3.84			-0.83	1.51	602.81	194.57			-6.89	4.19	14.64	0.26
Floors - Rms 104 & 110	1,11	6.76	4.04			-0.83	1.51	880.18	199.99			8.42	7.52	14.91	0.26
Floors - Rms 104 & 110	2,6	1.79	3.18			-0.83	1.51	1134.43	204.83			16.07	8.72	15.15	0.27
Floors - Rms 104 & 110	3,9	5.52	3.84			-0.83	1.51	695.27	196.39			0.76	6.09	14.96	0.26
Floors - Rms 104 & 110	4,7	3.03	3.42			-0.83	1.51	926.40	200.87			-1.79	5.53	14.43	0.26
Floors - Rms 104 & 110	5,4	8.00	4.23			-0.83	1.51	1196.06	205.98			5.87	7.08	14.49	0.26
Floors - Rms 104 & 110	5,12	9.24	4.41			1.93	3.14	1018.86	202.64			-1.79	5.53	17.54	0.29
Floors - Rms 104 & 110	6,5	3.03	3.42			-0.83	1.51	972.63	201.76			5.87	7.08	14.35	0.26
Floors - Rms 104 & 110	7,2	-0.70	2.65			-0.83	1.51	1003.45	202.35			-1.79	5.53	15.43	0.27
Floors - Rms 104 & 110	7,12	6.76	4.04			-0.83	1.51	795.43	198.35			0.76	6.09	14.39	0.26
Floors - Rms 104 & 110	8,8	3.03	3.42			-0.83	1.51	872.47	199.84			-1.79	5.53	14.75	0.26
Floors - Rms 104 & 110	9,3	5.52	3.84			-0.83	1.51	895.58	200.28			0.76	6.09	14.75	0.26
Floors - Rms 104 & 110	10,6	0.54	2.93			-0.83	1.51	864.77	199.69			10.96	7.94	14.86	0.26
Floors - Rms 104 & 110	11,4	1.79	3.18			1.93	3.14	1088.20	203.95			-1.79	5.53	14.97	0.26
Floors - Rms 104 & 110	12,7	0.54	2.93			-0.83	1.51	787.72	198.20			5.87	7.08	14.62	0.26
Floors - Rms 104 & 110	12,10	1.79	3.18			-0.83	1.51	918.70	200.73			5.87	7.08	13.82	0.25
Floors - Rms 104 & 110	13,5	1.79	3.18			-0.83	1.51	826.24	198.94			0.76	6.09	14.67	0.26
Floors - Rms 104 & 110	14,11	8.00	4.23			-0.83	1.51	1041.97	203.08			-4.34	4.91	14.81	0.26
Floors - Rms 104 & 110	14,2	5.52	3.84			-0.83	1.51	602.81	194.57			8.42	7.52	15.15	0.27
Floors - Rms 104 & 110	15,5	3.03	3.42			-0.83	1.51	864.77	199.69			3.31	6.60	12.88	0.24
Ceiling - Rms 104 & 110	1,5	2.30	3.11			-0.83	1.51	-2.55	178.44			-1.79	5.53		
Ceiling - Rms 104 & 110	2,8	-0.21	2.56			-0.83	1.51	127.47	181.21			3.31	6.60		
Ceiling - Rms 104 & 110	3,12	4.80	3.58			-0.83	1.51	471.64	108.33			13.52	8.34		
Ceiling - Rms 104 & 110	3,2	1.04	2.85			-0.83	1.51	127.47	181.21			3.31	6.60		
Ceiling - Rms 104 & 110	4,6	-0.21	2.56			1.93	3.14	112.17	180.88			13.52	8.34		
Ceiling - Rms 104 & 110	5,9	2.30	3.11			-0.83	1.51	112.17	180.88			8.42	7.52		
Ceiling - Rms 104 & 110	6,4	3.55	3.36			-0.83	1.51	12.75	178.77			0.76	6.09		
Ceiling - Rms 104 & 110	6,11	2.30	3.11			-0.83	1.51	127.47	181.21			-1.79	5.53		
Ceiling - Rms 104 & 110	7,1	8.57	4.19			-0.83	1.51	364.57	186.14			5.87	7.08		
Ceiling - Rms 104 & 110	8,3	3.55	3.36			-0.83	1.51	-2.55	178.44			10.96	7.94		
Ceiling - Rms 104 & 110	9,7	2.30	3.11			-0.83	1.51	203.95	182.81			-1.79	5.53		
Ceiling - Rms 104 & 110	9,12	7.31	4.00			1.93	3.14	242.19	183.61			-4.34	4.91		
Ceiling - Rms 104 & 110	10,5	2.30	3.11			-0.83	1.51	249.84	183.77			3.31	6.60		
Ceiling - Rms 104 & 110	11,2	3.55	3.36			-0.83	1.51	356.92	185.99			5.87	7.08		

T64L1DAT.WB1

SSWA-ZR-0001
Page 64
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 1

Page 2 of 3

SAMPLE NAME	GRID NAME	ALPHA (DPM/100CM2)				BETA (DPM/100CM2)				GAMMA (uR/hr)			
		TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV
Ceiling - Rms 104 & 110	11,11	1.04	2.85			-0.83	1.51	203.95	182.81			-1.79	5.53
Ceiling - Rms 104 & 110	12,9	2.30	3.11			1.93	3.14	112.17	180.88			10.96	7.94
Ceiling - Rms 104 & 110	13,2	4.80	3.58			15.68	6.90	379.86	186.46			5.87	7.08
Ceiling - Rms 104 & 110	14,3	2.30	3.11			1.93	3.14	410.46	187.08			3.31	6.60
Ceiling - Rms 104 & 110	15,1	6.06	3.79			1.93	3.14	349.27	185.83			13.52	8.34
Ceiling - Rms 104 & 110	14,10	4.80	3.58			-0.83	1.51	219.25	183.13			3.31	6.60
Wall North - Rm 110	1,3	8.57	4.19			7.43	5.00	-155.51	175.13			0.76	6.09
Wall North - Rm 110	3,2	12.33	4.72			1.93	3.14	188.66	182.49			3.31	6.60
Wall North - Rm 110	6,1	13.58	4.88			1.93	3.14	-17.85	178.11			0.76	6.09
Wall North - Rm 110	8,3	11.07	4.55			-0.83	1.51	-209.05	173.96			0.76	6.09
Wall North - Rm 110	10,4	8.57	4.19			-0.83	1.51	-239.65	173.29			0.76	6.09
Wall North - Rm 110	11,1	14.83	5.04			-0.83	1.51	12.75	178.77			5.87	7.08
Wall North - Rm 110	13,2	9.82	4.37			-0.83	1.51	-48.44	177.45			-4.34	4.91
Wall North - Rm 110	15,3	11.07	4.55			-0.83	1.51	-25.49	177.95			0.76	6.09
Wall East - Rm 110	18,4	14.83	5.04			-0.83	1.51	135.12	181.37			10.96	7.94
Wall East - Rm 110	19,1	17.34	5.34			1.93	3.14	96.88	180.56			5.87	7.08
Wall East - Rm 110	21,2	24.86	6.16			-0.83	1.51	181.01	182.33			-4.34	4.91
Wall East - Rm 110	23,2	11.07	4.55			1.93	3.14	-469.09	168.15			5.87	7.08
Wall East - Rm 110	25,2	11.07	4.55			4.68	4.17	181.01	182.33			10.96	7.94
Wall East - Rm 110	27,3	8.57	4.19			1.93	3.14	35.69	179.26			10.96	7.94
Wall South - Rm 110	2,3	12.33	4.72			-0.83	1.51	280.44	184.41			5.87	7.08
Wall South - Rm 110	4,2	12.33	4.72			1.93	3.14	280.44	184.41			5.87	7.08
Wall South - Rm 110	6,1	9.82	4.37			-0.83	1.51	356.92	185.99			0.76	6.09
Wall South - Rm 110	7-8,5	8.57	4.19			-0.83	1.51	127.47	181.21			0.76	6.09
Wall South - Rm 110	10,3	17.34	5.34			-0.83	1.51	150.42	181.69			3.31	6.60
Wall West - Rm 110	12,2	18.59	5.49			1.93	3.14	127.47	181.21			3.31	6.60
Wall West - Rm 110	14,3	6.06	3.79			-0.83	1.51	35.69	179.26			5.87	7.08
Wall West - Rm 110	16,2	12.33	4.72			1.93	3.14	35.69	179.26			3.31	6.60
Wall West - Rm 110	18,3	8.57	4.19			1.93	3.14	257.49	183.93			5.87	7.08
Wall West - Rm 110	20,1	12.33	4.72			-0.83	1.51	165.71	182.01			0.76	6.09
Wall West - Rm 110	22,4	11.07	4.55			-0.83	1.51	402.81	186.93			8.42	7.52
Wall West - Rm 110	23,3	13.58	4.88			-0.83	1.51	-10.20	178.28			-1.79	5.53
Wall East - Rm 104(deconned)	2,2	62.87	9.24	470.27	24.45	10.18	5.70	496.77	189.93	326	186	18.62	9.09
Wall East - Rm 104	4,2	12.33	4.72			1.93	3.14	265.14	184.09			5.87	7.08

T64L1DAT.WB1

SSWA-ZR-0001
Page 65
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 1

Page 3 of 3

SAMPLE NAME	GRID NAME	ALPHA (DPM/100CM2)			BETA (DPM/100CM2)			GAMMA (uR/hr)		
		TOTAL	STD DEV	MAX	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV
Wall South - Rm 104(deconned)	5,1	13.83	4.87	282.91	19.03	1.93	249.03	184.81	117	182
Wall West - Rm 104	8,3	8.57	4.19		-0.83	1.51	-86.68	176.63		182
Wall West - Rm 104	10,1	41.15	7.64		23.93	8.39	58.64	179.75		
Wall North - Rm 104	12,3	12.33	4.72		-0.83	1.51	196.30	182.65		
Wall North - Rm 104	14,2-3	9.82	4.37		1.93	3.14	35.69	179.26		
Structure - Trusses Rm 104	St-1	193.64	15.81		1.93	3.14	450.32	188.98		
Structure - Trusses Rm 104	St-2	164.72	14.61		-0.83	1.51	411.61	188.18		
Structure - Trusses Exit Rm 110	St-3	57.84	8.89		7.43	5.00	-316.13	172.57		
Structure - Trusses NE corner Rm 110	St-4	98.08	11.39		-0.83	1.51	434.84	188.66		
Structure - Trusses near C(4,10)	St-5	57.84	8.89		1.93	3.14	388.39	187.70		
Structure - Trusses near Center	St-6	44.01	7.85		-0.83	1.51	272.26	185.29		
Structure - Trusses C(6,4) near HTR	St-7	26.41	6.29		1.93	3.14	365.16	187.23		
Structure - Beam Ledges - West	Sb-1	94.30	11.18		4.68	4.17	-99.35	177.36		
Structure - Beam Ledges - Center West	Sb-2	44.01	7.85		1.93	3.14	-153.55	176.17		
Structure - Beam Ledges - Center	Sb-3	71.67	9.82		4.68	4.17	101.94	181.70		
Structure - Beam Ledges - Center East	Sb-4	137.06	13.37		-0.83	1.51	148.39	182.69		
Structure - Beam Ledges - East	Sb-5	155.92	14.23		-0.83	1.51	233.55	184.48		
Structure - Heater Outside Wall	Sh-1	5.03	3.56		-0.83	1.51	-21.94	179.04		
Structure - Heater Inside Grating	Sh-2	2.51	3.08		1.93	3.14	24.52	180.04		
Structure - Heater Inside Wall	Sh-3	0.00	2.51		-0.83	1.51	-230.97	174.47		

SSWA-ZR-0001

Page 66

01/14/94

T64L11DAT.WB1

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 2

Page 1 of 3

SAMPLE NAME	GRID NAME	ALPHA (DPM/100CM2)				BETA (DPM/100CM2)				GAMMA (uR/h)			
		TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV
Floors - Rm 114	1,4	0.54	2.93			1.93	3.14	976.67	207.22			5.87	7.08
Floors - Rm 114	2,1	-0.70	2.65			-0.83	1.51	1016.64	207.99			3.31	6.60
Floors - Rm 114	3,7	4.27	3.64			-0.83	1.51	680.87	201.43			-1.79	5.53
Floors - Rm 114	2,10	-3.18	1.99			-0.83	1.51	928.70	206.29			3.31	6.60
Floors - Rm 114	5,12	1.79	3.18			-0.83	1.51	1096.58	209.52			-4.34	4.91
Floors - Rm 114	4,5	5.52	3.84			-0.83	1.51	864.74	205.05			10.96	7.94
Floors - Rm 114	5,2	1.79	3.18			-0.83	1.51	816.78	204.11			-1.79	5.53
Floors - Rm 114	6,6	0.54	2.93			-0.83	1.51	952.68	206.75			8.42	7.52
Floors - Rm 114	7,3	3.03	3.42			-0.83	1.51	736.83	202.54			5.87	7.08
Floors - Rm 114	8,8	-0.70	2.65			-0.83	1.51	1104.58	209.67			0.76	6.09
Floors - Rm 114	7,11	-0.70	2.65			-0.83	1.51	928.70	206.29			-1.79	5.53
Floors - Rm 114	9,4	3.51	3.75			-0.83	1.51	776.23	203.67			8.42	7.52
Floors - Rm 114	10,1	2.27	3.54			-0.83	1.51	480.77	197.95			8.42	7.52
Floors - Rm 114	11,7	4.75	3.95			-0.83	1.51	690.70	202.03			8.42	7.52
Floors - Rm 114	12,6	3.51	3.75			-0.83	1.51	791.78	203.97			-1.79	5.53
Floors - Rm 114	12,10	3.51	3.75			1.93	3.14	325.26	194.87			3.31	6.60
Floors - Rm 114	13,1	5.99	4.14			-0.83	1.51	535.19	199.02			0.76	6.09
Floors - Rm 114	14,5	4.75	3.95			-0.83	1.51	589.62	200.08			-1.79	5.53
Floors - Rm 114	15,2	2.27	3.54			-0.83	1.51	426.34	196.88			0.76	6.09
Floors - Rm 114	15,11	2.27	3.54			1.93	3.14	706.25	202.33			3.31	6.60
Ceiling - Rm 114	1,1	0.83	3.39			-0.83	1.51	-98.11	172.46			5.87	7.08
Ceiling - Rm 114	2,4	3.33	3.82			1.93	3.14	-186.41	170.56			-1.79	5.53
Ceiling - Rm 114	3,6	0.83	3.39			-0.83	1.51	-385.07	166.22			10.96	7.94
Ceiling - Rm 114	4,3	2.08	3.61			-0.83	1.51	-215.84	169.93			-1.79	5.53
Ceiling - Rm 114	5,2	3.33	3.82			-0.83	1.51	-46.60	173.55			5.87	7.08
Ceiling - Rm 114	6,6	-2.92	2.60			1.93	3.14	-333.57	167.36			3.31	6.60
Ceiling - Rm 114	7,7	5.83	4.21			-0.83	1.51	-421.86	165.41			-4.34	4.91
Ceiling - Rm 114	8,9	-0.42	3.15			-0.83	1.51	-318.85	167.68			5.87	7.08
Ceiling - Rm 114	9,4	3.33	3.82			1.93	3.14	-186.41	170.56			3.31	6.60
Ceiling - Rm 114	10,5	4.58	4.02			-0.83	1.51	-245.27	169.29			-1.79	5.53
Ceiling - Rm 114	11,9	0.83	3.39			-0.83	1.51	-259.99	168.97			3.31	6.60
Ceiling - Rm 114	12,2	3.33	3.82			-0.83	1.51	-259.99	168.97			-1.79	5.53
Ceiling - Rm 114	13,4	0.83	3.39			1.93	3.14	-399.79	165.90			3.31	6.60

T64L2DAT.WB1

SSWA-ZR-0001
Page 67
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 2

Page 2 of 3

				ALPHA							BETA					GAMMA	
SAMPLE	GRID			(DPM/100CM2)							(DPM/100CM2)				(uR/h)		
NAME	NAME	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV		
Ceiling - Rm 114	14,7	2.08	3.61			-0.83	1.51	-31.89	173.87			10.96	7.94				
Ceiling - Rm 114	15,6	-1.67	2.89			1.93	3.14	-245.27	169.29			0.76	6.09				
Ceiling - Rm 114	13,12	4.58	4.02			-0.83	1.51	-120.18	171.99			-1.79	5.53				
Ceiling - Rm 114	10,10	3.33	3.82			-0.83	1.51	-318.85	167.68			3.31	6.60				
Ceiling - Rm 114	8,12	0.83	3.39			-0.83	1.51	-105.47	172.30			0.76	6.09				
Ceiling - Rm 114	4,11	-1.67	2.89			-0.83	1.51	-83.39	172.77			-6.89	4.19				
Ceiling - Rm 114	1,10	-1.67	2.89			1.93	3.14	-245.27	169.29			-1.79	5.53				
Wall - South Rm 114	3,1	3.50	3.31			-0.83	1.51	289.14	193.50			5.87	7.08				
Wall - South Rm 114	4,4	3.50	3.31			-0.83	1.51	-2.47	175.03			-1.79	5.53				
Wall - South Rm 114	5,2	1.03	2.81			-0.83	1.51	9.33	187.63			10.96	7.94				
Wall - South Rm 114	8,3	-0.21	2.52			-0.83	1.51	-142.57	184.37			-4.34	4.91				
Wall - South Rm 114	8,5	-0.21	2.52			-0.83	1.51	-158.31	171.69			0.76	6.09				
Wall - South Rm 114	10,1	2.26	3.07			-0.83	1.51	-94.60	185.40			-1.79	5.53				
Wall - South Rm 114	11,4	2.26	3.07			-0.83	1.51	34.63	175.81			-4.34	4.91				
Wall - South Rm 114	13,3	-0.21	2.52			-0.83	1.51	-2.47	175.03			-4.34	4.91				
Wall - South Rm 114	15,5	1.03	2.81			-0.83	1.51	108.84	177.37			0.76	6.09				
Wall - West Rm 114	17,2	2.26	3.07			-0.83	1.51	696.86	201.75			5.87	7.08				
Wall - West Rm 114	20,2	2.26	3.07			-0.83	1.51	760.81	203.01			-1.79	5.53				
Wall - West Rm 114	23,1	0.40	2.88			-0.83	1.51	528.97	198.39			-1.79	5.53				
Wall - West Rm 114	26,3	0.40	2.88			-0.83	1.51	399.53	195.50			8.42	7.52				
Wall - West Rm 114	21,4	-0.21	2.52			-0.83	1.51	160.78	178.46			3.31	6.60				
Wall - West Rm 114	25,4	0.40	2.88			-0.83	1.51	524.39	185.86			0.76	6.09				
Wall - North Rm 114	2,2	3.50	3.31			-0.83	1.51	744.82	202.69			8.42	7.52				
Wall - North Rm 114	4,3	0.40	2.88			1.93	3.14	212.73	179.53			8.42	7.52				
Wall - North Rm 114	7,1	-1.44	2.20			-0.83	1.51	680.87	201.43			0.76	6.09				
Wall - North Rm 114	10,3	-0.81	2.61			-0.83	1.51	294.35	181.21			0.76	6.09				
Wall - North Rm 114	13,1	-1.44	2.20			1.93	3.14	664.88	201.11			-1.79	5.53				
Wall - North Rm 114	3,4	2.82	3.35			-0.83	1.51	695.07	189.24			-1.79	5.53				
Wall - North Rm 114	9,5	1.61	3.12			-0.83	1.51	93.99	177.06			8.42	7.52				
Wall - North Rm 114	11,4	1.03	2.81			-0.83	1.51	635.70	188.07			-6.89	4.19				
Wall - North Rm 114	15,4	4.03	3.56			-0.83	1.51	301.77	181.36			-1.79	5.53				
Wall - East Rm 114	17,2	2.26	3.07			-0.83	1.51	305.12	193.83			8.42	7.52				
Wall - East Rm 114	20,2	-0.21	2.52			-0.83	1.51	385.07	195.47			-4.34	4.91				

T64L2DAT.WB1

SSWA-ZR-0001
Page 68
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 2

Page 3 of 3

SAMPLE NAME	GRID NAME	ALPHA (DPM/100CM2)				BETA (DPM/100CM2)				GAMMA (uR/h)			
		TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV
Wall - East Rm 114	23,1	2.43	2.33			-0.83	1.51	3.53	152.45			3.31	6.60
Wall - East Rm 114	26,1	1.03	2.81			-0.83	1.51	272.09	180.76			0.76	6.09
Wall - East Rm 114	19,1	5.04	2.78			-0.83	1.51	1004.76	174.07			5.87	7.08
Wall - East Rm 114	27,4	1.61	3.12			-0.83	1.51	606.02	187.48			-6.89	4.19
Structure - Trusses Rm 114 NW	St-1	1.68	3.25			-0.83	1.51	-315.27	183.36			0.76	6.09
Structure - Trusses Rm 114 Center	St-2	0.42	3.00			-0.83	1.51	-26.72	189.57			10.96	7.94
Structure - Trusses Rm 114 SE	St-3	2.94	3.49			-0.83	1.51	-10.69	189.90			3.31	6.60
Structure - Beams Rm 114 North	Sb-1	6.72	4.11			-0.83	1.51	-146.95	187.01			0.76	6.09
Structure - Beams Rm 114 Center	Sb-2	4.20	3.71			-0.83	1.51	-34.73	189.40			-4.34	4.91
Structure - Beams Rm 114 South	Sb-3	11.76	4.82			-0.83	1.51	77.48	191.76			-4.34	4.91
Maximum:		11.76	4.82			1.93	3.14	1104.58	209.67			10.96	7.94
Minimum:		-3.18	1.99			-0.83	1.51	-421.86	152.45			-6.89	4.19
Average:		1.91	3.23			-0.43	1.74	269.40	186.41			1.84	6.23

T64L2DAT.WB1

SSWA-ZR-0001
Page 69
01/14/94

01/14/94

BUILDING 064 - FINAL SURVEY CALCULATED RESULTS FOR LOT 3

Page 1 of 1

				ALPHA							BETA				GAMMA	
SAMPLE	GRID			(DPM/100CM2)							(DPM/100CM2)				(uR/h)	
NAME	NAME	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	MAX	STD DEV	REM	STD DEV	TOTAL	STD DEV	
Floors - Rm 116	F-1	4.20	3.71			-0.83	1.51	1247.73	214.83			10.96	7.94	17.32	0.28	
Floors - Rm 116	F-2	53.33	8.70			-0.83	1.51	1207.65	214.08			10.96	7.94	13.30	0.25	
Ceiling - Rm 116	C-1	-0.84	2.72			1.93	3.14	117.56	192.59			-1.79	5.53			
Wall - West Rm 116	2,2	-0.84	2.72			4.68	4.17	887.04	207.99			5.87	7.08			
Wall - North Rm 116	5,1	0.42	3.00			-0.83	1.51	1191.62	213.78			-4.34	4.91			
Wall - East Rm 116	7,3	1.68	3.25			-0.83	1.51	782.84	205.97			3.31	6.60			
Wall - South Rm 116	10,2	4.20	3.71			-0.83	1.51	229.77	194.91			0.76	6.09			
Floors - Rm 120	3,1	7.02	3.98			-0.83	1.51	743.97	194.38			-1.79	5.53	13.24	0.25	
Floors - Rm 120	4,3	9.50	4.35			-0.83	1.51	539.35	190.35			-1.79	5.53	11.23	0.23	
Floors - Rm 120	7,3	28.08	6.48			-0.83	1.51	546.92	190.50			0.76	6.09	11.14	0.23	
Floors - Rm 120	8,1	45.42	7.96			-0.83	1.51	599.97	191.55			3.31	6.60	9.48	0.21	
Ceiling - Rm 120	1,4	3.30	3.35			-0.83	1.51	-271.57	173.46			0.76	6.09			
Ceiling - Rm 120	3,1	3.30	3.35			-0.83	1.51	-13.89	179.00			-1.79	5.53			
Wall - West Rm 120	1,2	2.06	3.12			-0.83	1.51	-423.14	170.11			8.42	7.52			
Wall - West Rm 120	4,3	5.78	3.78			1.93	3.14	-301.88	172.79			3.31	6.60			
Wall - East Rm 120	9,1	0.83	2.86			-0.83	1.51	16.42	179.64			-1.79	5.53			
Wall - East Rm 120	12,2	0.83	2.86			-0.83	1.51	-362.51	171.46			26.27	10.10			
Wall - South Rm 120	14,1	-1.65	2.26			-0.83	1.51	-612.61	165.84			-1.79	5.53			
Floors - Restroom	F-1	13.21	4.85			-0.83	1.51	569.66	190.95			10.96	7.94	10.23	0.22	
Ceiling - Restroom	C-1	-0.41	2.58			-0.83	1.51	-377.67	171.12			3.31	6.60			
Wall - West Restroom	3,2	11.97	4.69			-0.83	1.51	-210.94	174.77			-4.34	4.91			
Wall - North Restroom	5,2	35.51	7.15			-0.83	1.51	289.25	185.30			-1.79	5.53			
Wall - East Restroom	7,1	-0.41	2.58			-0.83	1.51	8.84	179.48			8.42	7.52			
Maximum:		53.33	8.70			4.68	4.17	1247.73	214.83			26.27	10.10	17.32	0.28	
Minimum:		-1.65	2.26			-0.83	1.51	-612.61	165.84			-4.34	4.91	9.48	0.21	
Average:		9.85	4.09			-0.35	1.76	278.45	188.04			3.31	6.49	12.28	0.24	

SSWA-ZR-0001
Page 70
01/14/94

T64L3DAT.WB1

Gamma exposure rate in Bldg. 445

counts/1 min	uR/hr	uncertainty
3205	14.91	0.26
3189	14.83	0.26
3362	15.64	0.27
3366	15.66	0.27
3149	14.65	0.26
3194	14.86	0.26
3187	14.82	0.26
3109	14.46	0.26
3261	15.17	0.27
3365	15.65	0.27
3150	14.65	0.26
3181	14.80	0.26
3183	14.80	0.26
3237	15.06	0.26
3252	15.13	0.27
3380	15.72	0.27
3179	14.79	0.26
3231	15.03	0.26
3264	15.18	0.27
3242	15.08	0.26
3322	15.45	0.27
3274	15.23	0.27
3263	15.18	0.27
3191	14.84	0.26
3336	15.52	0.27
3228	15.01	0.26
3275	15.23	0.27
3174	14.76	0.26
3209	14.93	0.26
3212	14.94	0.26
3162	14.71	0.26
3264	15.18	0.27
3144	14.62	0.26
2794	13.00	0.25
3332	15.50	0.27
3277	15.24	0.27
3219	14.97	0.26
3376	15.70	0.27
3191	14.84	0.26
3049	14.18	0.26

BUILDING 064 - FINAL SURVEY CALCULATED DAILY INSTRUMENT BACKGROUNDS

	Instrument Background Qualification Data				
DATE	BKGD-A	EFACT-A	BKGD-B	EFACT-B	
	AVE for 5 min		AVE for 5 min		
07-Sep-93	2.563	4.407	279.759	7.705	ave plex
08-Sep-93	2.563	4.407	279.759	7.705	ave plex
09-Sep-93	2.563	4.407	279.759	7.705	ave plex
10-Sep-93	2.563	4.407	279.759	7.705	ave plex
14-Sep-93	2.167	4.445	272.333	7.648	
15-Sep-93	2.000	4.459	268.833	7.742	
16-Sep-93	2.563	4.407	274.833	7.995	
17-Sep-93	3.167	4.394	293.167	7.775	
20-Sep-93	2.167	4.379	278.333	7.421	
21-Sep-93	2.667	4.290	287.833	7.808	
22-Sep-93	3.333	4.434	281.333	7.358	
23-Sep-93	2.667	4.467	281.333	8.015	
24-Sep-93	2.333	4.393	279.833	7.579	
ave plex	0.513	4.407	55.952	7.705	

Energy Technology Engineering Center		DOCUMENT CHANGE RECORD		LEDGER	G.O.	SUBACCT.	No
DOC NO. 7593-EL 250113		REV. G	PROJECT: SCTI	29841	53596	87507	16097
SPECIFIC CHANGE REQUIRED: <div style="text-align: center; margin: 10px 0;"> </div>				PROCEED IMMEDIATELY <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO SDD CHANGE REQUIRED <input type="checkbox"/> YES <input checked="" type="checkbox"/> NO ACTION BY: CONST. <input type="checkbox"/> TEST <input checked="" type="checkbox"/> OTHER _____ AGREED BY: <i>Ralph Smith</i> ACTION COMPLETE SDD CHG BY: _____ PROGRAM MGR. <i>W. H. H.</i> REQUESTER R. S. HOMER ORIGINATOR R. S. HOMER MGR TECH DOC ORIG <i>J. H. Bennett</i> 2-10-94 CHECKER <i>R. K. Nakuta</i> 10-19-93 FAC. PROJ. ENGR. <i>Amato</i> 2-10-94 QUALITY ENGR. <i>DeMone</i> 2-10-94 ASU DATA CLERK			
REASON FOR CHANGE: <div style="text-align: center; margin: 10px 0;"> <u>TEST STAND 1</u> NEW AIR DRYER </div>				OTHER DOCUMENTS CHANGED BY THIS DCR: <div style="text-align: center; margin: 10px 0;"> 355-ED-250 </div>			

DATE: 8-19-96

D/092 INCOMING

ENVIRONMENTAL

[illegible]

Dist by ENVIR Corresp. X68132

REVISÉD 8-29-96

With Enclosure

* Distrubution in Advance

INENVIR

* *Our e-mail address is listed as Correspondence in the Global Address List

DEPARTMENT OF HEALTH SERVICES

714/744 P STREET

P.O. BOX 942732

SACRAMENTO, CA 94234-7320



(916) 323-2759

August 19, 1996



Mr. Phil Rutherford, Manager
Environmental Remediation
Rocketdyne Division
Rockwell International Corporation
P. O. Box 7930
Canoga Park, CA 91309-7930

Subject: Demolition and Disposal of Structural Material from
Building T064 at SSFL

Dear Mr. Rutherford:

This letter is to acknowledge the receipt of your letter dated July 30, 1996, with attachments, requesting concurrence of the above subject. Based on the review of your submittal and the results of the surveys performed by the inspection staff of our Los Angeles office, the Radiologic Health Branch (RHB) concurs that you may proceed with the demolition of the Building T064 and that you also may dispose of the structural material resulting from such demolition as conventional waste.

If you have any questions concerning this matter, please feel free to call Mr. Stephen Hsu of this office at (916) 322-4797.

Sincerely,

Gerard Wong, Ph.D., Chief
Radioactive Material Licensing Section
Radiologic Health Branch

007284 RC

Oliver, Brian M.

From: Gerard Wong
To: bmoliver@rocket.rdyne.rockwell.com
Subject: T064 Building Debris Disposal
Date: Thursday, August 22, 1996 3:47PM

*** Reply to note of 08/21/96 16:06

We sent you a letter dated 8/19/96 concurring to the disposal of materials as a result from demolition of Bldg T064.

ETEC LETTER REVIEW RECORD

LTR.No.: 96 ETEC-DRF- 0413 File Name: _____ Disk No.: _____ Date: 07-30-96

Subject: Demolition and Disposal of Structural Material from Building T064 at SSFL _____

Addressee: G. Wong Signed by: P. D. Rutherford

Prepared by: B. Oliver Typed by: B. Oliver

Related G.O. No.: _____ Completes Action in: DRF- _____ Req. Action by: ETEC _____ Other _____ None _____

Remarks:

Approvals-

_____ Director & Program Mgr : _____ Director Operations: _____ Mgr. Gen. Programs: _____ Mgr. Fac. Support: _____ Mrg. EM Pump:	_____ Mgr., Business Mgmt: _____ XPgm. Mgr. Env Mgmt: <i>Wong</i> _____ Mgr. Env Mgmt: _____ Mgr. PPTF: _____ Mgr. Progress Dev.: <i>- Mgr Env Ren POR</i>
--	---

- Distribution -

Without Enclosure (/)		With Enclosure (X)			
<u>Akamine, K. S.</u> T039	<u>Heslin, S. R.</u> T038	<u>Reeder, S. E.</u> T019	<u>Rochelle, D. R.</u> T039	<u>1 Barnes</u>	<u>T100</u>
<u>Albert, A.</u> T019	<u>Hodge, S. E.</u> T019	<u>Ruffino, K.</u> T038	<u>Roy, J. J.</u> T006		
<u>Alpert, E. E.</u> T038	<u>Homer, R. S.</u> T039	<u>Ruffino, K.</u> T038	<u>Rutherford, P. D.</u> T436		
<u>Amar, R. C.</u> T038	<u>Horton, P. H.</u> T038	<u>Sahagian, D. H.</u> T038	<u>Samuels, S. L.</u> T038		
<u>Ampaya, J. P.</u> T006	<u>Ingersoll, R. D.</u> T038	<u>Santa Ines, R.</u> T039	<u>Schmidt, T. E.</u> T462		
<u>Atkinson, R. F.</u> T334	<u>Jaquay, K. R.</u> T013	<u>Sena, D. B.</u> T006	<u>Shah, S.</u> T038		
<u>Aubuchon, D. F.</u> T355	<u>Jassak, R. M.</u> T013	<u>Sinclair, R. M.</u> T355	<u>Stellman, D.</u> T006		
<u>Bassat, I. B.</u> T034	<u>Jetter, R. I.</u> T038	<u>Stone, L. R.</u> T038	<u>Subbaraman, G.</u> T038		
<u>Beamer, S. K.</u> T038	<u>Kneff, D. W.</u> T038	<u>Sujata, B.</u> T038	<u>Tapia, D. G.</u> T355		
<u>Berreth, J. M.</u> T039	<u>Knudsen, K. T.</u> T038	<u>Trippeda, D. M.</u> T020	<u>Ueshiro, R. L.</u> T436		
<u>Berwager, L. E.</u> T462	<u>Kramer, S.</u> T038	<u>VandenHeuvel, R.</u> T038	<u>VanLeeuwen, R.</u> T334		
<u>Blandino, P.</u> SS14	<u>Lafflam, S. R.</u> AA24	<u>Waite, P.</u> T059	<u>Wells, T. L.</u> T013		
<u>Boggio, J. M.</u> T462	<u>Langowski, T. J.</u> T039	<u>A/C Coordinator</u> T038	<u>X DRF Control *</u> T038		
<u>Chen, W. P.</u> T038	<u>Larson, D. A.</u> T013	<u>Library</u> T038	<u>1 Elstrom</u> T100		
<u>Cleveland, J. R.</u> T355	<u>Lee, M. E.</u> T038	<u>1 Tuttle</u> T100			
<u>Darley, D. K.</u> T462	<u>Limlamai, M.</u> T038				
<u>DeBear, W. S.</u> T038	<u>Makuta, R. K.</u> T039				
<u>Doerr, S. M.</u> T039	<u>Marshall, R. A.</u> T034				
<u>Ervin III, G.</u> T038	<u>McDowell, M. W.</u> T038				
<u>Finch, M.</u> T038	<u>Meyer, R. D.</u> T038				
<u>Fuentes, G. L.</u> T133	<u>Moore, R. M.</u> T038				
<u>Fusselman, S.P.</u> T006	<u>Murkherjee, N.</u> SS14				
<u>Gabler, M.</u> T038	<u>Newcomb, J. C.</u> T006				
<u>Gay, R. L.</u> T006	<u>Ohara, P. S.</u> T038				
<u>Gaylord, G. G.</u> AA24	<u>Oliver, B.</u> T100				
<u>Gerritsen, W. J.</u> T355	<u>Olson, P.</u> T038				
<u>Green, P. M.</u> T038	<u>Onesto, A. T.</u> T013				
<u>Grimmett, D. L.</u> T006	<u>Pascolla, A. L.</u> T038				
<u>Guon, J.</u> T006	<u>Peterson, E. V.</u> T038				
<u>Hardy, R.</u> T038					



July 30, 1996

In reply refer to 96ETEC-DRF-0413

Dr. Gerard Wong
Radiologic Health Branch
Radioactive Materials Licensing
State of California Department of Health Services
601 N. 7th Street
P.O. Box 942732
Sacramento, CA 94234

Subject: Demolition and Disposal of Structural Material from Building T064 at SSFL

Reference: "Final Radiological Report of Building 064 Interior", ETEC Document SSWA-ZR-0001, January 1994.

Dear Dr. Wong:

As you may be aware, DOE has given approval for the release and demolition of Building T064 at the Santa Susana Field Laboratories (SSFL) in FY97 (Enclosure A). The remaining land is to be combined with the T064 Sideyard into one site for subsequent completion of remediation efforts and eventual release.

Building T064 was surveyed by Rocketdyne in 1993 and the results reported in 1994 (Reference). The results of that survey indicated that the building met all of the requirements of the DOE, the NRC, and the State of California for release without radiological restriction. An independent verification survey of T064 was subsequently conducted by the Oak Ridge Institute for Science and Education (ORISE) and the State in July 1994. One small area was identified by ORISE with contamination above guideline levels, and this area was remediated by Rocketdyne/ETEC personnel to below guideline levels. Subsequent to this remediation, ORISE agreed that T064 met DOE requirements for unrestricted release (Enclosure B). The State has also verbally concurred with the results of these surveys.

Based on the above surveys and releases, it is our understanding that the materials from the demolition of this building may be disposed of as conventional waste. As we are currently in the planning stages for this demolition, we would appreciate it if you would advise us as soon as possible if this understanding is correct.

July 30, 1996

Page 2

Should you have any questions, or require additional information, please contact the undersigned at (818) 586-6140 or at pdruther@rdyne.rockwell.com.

Very Truly Yours



Phil Rutherford, Manager
Environmental Remediation

Enclosures:

- A. "Demolition of Building 064", DOE-Oakland Letter dated June 25, 1996, M. Lopez to M. Lee (enclosed).
- B. "Verification Survey of Buildings 005, 023, and 064, Santa Susana Field Laboratories, Rockwell International, Ventura County, California", ORISE Report 94/K-14, October 1994.

cc without enclosure

M. E. Lopez DOE-OAK

Oliver, Brian M.

From: Rutherford, Philip D.
To: Lee, Majelle E.; Oliver, Brian M.; Horton, Philip H.; Hardy, Robert B.; Tuttle, Robert J.
Subject: RE: 4064
Date: Friday, July 26, 1996 10:25AM

As we discussed on Friday, both ORISE and the State have surveyed the 064 building. ORISE have documented as clean. State has verbally said it is clean but have not documented this in a letter (to my knowledge). DOE approved demolition in June by letter. We will discuss disposal of above ground 064 rubble as clean waste to landfill with the State next week when they are here and solicit their written concurrence. We will however have to survey/sample under the concrete foundation and drain pipes.

From: Hardy, Robert B.
To: Rutherford, Philip D.
Cc: Tuttle, Robert J.; Oliver, Brian M.; Lee, Majelle E.; Horton, Philip H.
Subject: 4064
Date: Thursday, July 25, 1996 2:13PM
Priority: High

Phil,

You are probably aware that building 4064 is currently scheduled to be demolished in FY 97. The understanding that I have is that the building has been free released by ORISE and DHS. If this is true, can the building be rubbleized and disposed of as clean waste? I am currently working on a SOW to demolish this building by a excavator (Big Back Hoe) and break up all the concrete (with the exception of the floor and foundation which will be handled by D/022). The material will be haul it off the hill and disposed of as clean waste . It is necessary that we know all the road blocks, before we proceed with the SOW.

thanks
Bob



96ETEC-DRF0322

Department of Energy

Oakland Operations Office
1301 Clay Street, N700
Oakland, CA 94612-5208

June 25, 1996

Majelle Lee
Program Manager
Environmental Programs
Energy Technology Engineering Center
Rocketdyne Division
Rockwell International Corporation
P.O. Box 7930
Canoga Park, CA 91309-7930

Subject: Demolition of Building 064

Dear Ms. Lee:

The cleanup of radioactive decontamination at Building 064 is complete. ORISE has verified the condition of the building. Consequently, approval is given for the demolition of B064. The empty site (the land) will be combined with the B064 Sideyard into one release site. This release site is expected to be ready for a release for unrestricted use in FY97, after the remediation of the Sideyard is completed.

Sincerely,

A handwritten signature in cursive script, reading "Michael Lopez", is positioned above the typed name.

Michael Lopez
ETEC PM
Environmental
Restoration Division

Date: 07-01-96
 DRF No. 96ETEC-DRF-0322
 Distribution List - Environmental Management

From: Department of Energy
 To: Majelle Lee

- Distribution -

__Akamine, K. S.	T039	__Heslin, S. R.	T038	__Reeder, S. E.	T019
__Albert, A.	T019	__Hodge, S. E.	T019	__Rochelle, D. R.	T039
__Alpert, E. E.	T038	__Homer, R. S.	T039	__Ruffino, K.	T038
_/Amar, R. C.	T038	_/Horton, P. H.	T038	__Roy, J. J.	T006
__Ampaya, J. P.	T006	__Ingersoll, R. D.	T038	__Ruffino, K.	T038
__Atkinson, R. F.	T334	__Jaquay, K. R.	T013	_/Rutherford, P. D.	T436
__Aubuchon, D. F.	T355	__Jassak, R. M.	T013	__Sahagian, D. H.	T038
__Bassat, I. B.	T034	__Kneff, D. W.	T038	__Samuels, S. L.	T038
__Beamer, S. K.	T038	__Knudsen, K. T.	T038	__Santa Ines, R.	T039
__Berreth, J. M.	T039	__Kramer, S.	T038	__Schmidt, T. E.	T462
__Berwager, L. E.	T462	__Lafflam, S. R.	AA24	__Sena, D. B.	T006
__Boggio, J. M.	T462	__Langowski, T. J.	T039	__Shah, S.	T038
__Chen, W. P.	T038	__Larson, D. A.	T013	__Sinclair, R. M.	T355
__Darley, D. K.	T462	_/Lee, M. E.	T038	__Stellman, D.	T006
__DeBear, W. S.	T038	__Limlamai, M.	T038	__Stone, L. R.	T038
__Doerr, S. M.	T039	__Makuta, R. K.	T039	__Subbaraman, G.	T038
__Ervin III, G.	T038	__Marshall, R. A.	T034	__Sujata, B.	T038
__Finch, M.	T038	__McDowell, M. W.	T038	__Tapia, D. G.	T355
__Fuentes, G. L.	T133	_/Meyer, R. D.	T038	__Trippeda, D. M.	T020
__Fusselman, S.P.	T006	__Moore, R. M.	T038	__Ueshiro, R. L.	T436
_/Gabler, M.	T038	__Murkherjee, N.	SS14	__VandenHeuvel, R.	T038
__Gay, R. L.	T006	__Newcomb, J. C.	T006	__VanLeeuwen, R.	T334
__Gaylord, G. G.	AA24	__Ohara, P. S.	T038	__Waite, P.	T059
__Gerritsen, W. J.	T355	_/Oliver, B.	T100	__Wells, T. L.	T013
__Green, P. M.	T038	__Olson, P.	T038	__A/C Coordinator	T038
__Grimmett, D. L.	T006	__Onesto, A. T.	T013	X DRF Control *	T038
__Guon, J.	T006	__Pascolla, A. L.	T038	__Library	T038
_/Hardy, R.	T038	__Peterson, E. V.	T038		